



PhilGEPS

Philippine Government Electronic Procurement System

Central Portal for
Philippine Government
Procurement Opportunities

[Help](#)

Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number 8028015
Procuring Entity CARLOS HILADO MEMORIAL STATE COLLEGE
Title Procurement of Labor and Materials for Conversion of Old Clinic to Gender and Development Child Minding Facility - Alijis Campus
Area of Delivery Negros Occidental

Solicitation Number:	RFQ 21-288	Status	Pending
Trade Agreement:	Implementing Rules and Regulations	Associated Components	1
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	Bid Supplements	0
Classification:	Civil Works	Document Request List	0
Category:	Construction Projects	Date Published	25/09/2021
Approved Budget for the Contract:	PHP 499,934.41	Last Updated / Time	24/09/2021 11:39 AM
Delivery Period:	60 Day/s	Closing Date / Time	04/10/2021 10:00 AM
Client Agency:			
Contact Person:	Rowena De la Vida Prado Administrative Assistant II Mabini Street Talisay City Negros Occidental Philippines 6115 63-34-7124804 63-34-7128404 bac.sec@chmsc.edu.ph		

Description

Republic of the Philippines
 CARLOS HILADO MEMORIAL STATE COLLEGE
 Talisay City, Negros Occidental
 Telefax: (034) 712-8404 / 495-3767
 bac.sec@chmsc.edu.ph

REQUEST FOR QUOTATION
 Page 1 of 12
 Date: September 23, 2021
 Quotation No. 21-288

Please quote your lowest price on the item/s listed below, stating the shortest time of delivery and submit your quotation duly signed by your representative not later than _____ in the return envelope attached herewith.

EDWIN H. BUGNA, Ph.D.- T.M.
 BAC Chairman

NOTE:

- ALL ENTRIES MUST BE TYPEWRITTEN
- DELIVERY PERIOD WITHIN _____ CALENDAR DAYS
- WARRANTY SHALL BE FOR A PERIOD OF SIX (6) MONTHS FOR SUPPLIES & MATERIALS, ONE (1) YEAR FOR EQUIPMENT, FROM DATE OF ACCEPTANCE BY THE PROCURING ENTITY

4. PRICE VALIDITY SHALL BE FOR A PERIOD OF _____ CALENDAR DAYS
5. G-EPS REGISTRATION CERTIFICATE SHALL BE ATTACHED UPON SUBMISSION OF THE QUOTATION
6. BIDDERS SHALL SUBMIT ORIGINAL BROCHURES SHOWING CERTIFICATIONS OF THE PRODUCT BEING OFFERED

ITEM DESCRIPTION OF WORKS QTY. UNIT MATERIAL COST LABOR COST TOTAL COST
 NO. Unit Cost Material Sub-Total Cost Unit Cost Labor Sub-Total Cost
 ONE (1) LOT
 CONVERSION OF OLD CLINIC TO GENDER AND DEVELOPMENT CHILD MINDING FACILITY

Scope of Works:

Demolition Works

GENERAL REQUIREMENTS

Demolition Works

CARPENTRY WORKS

FORM WORKS

FABRICATION OF MOVABLE COUNTER SINK

Construction of Wall partition (for breast feeding area)

FABRICATION of Padded Partition low wall

INSTALLATION OF PANEL DOORS

Ceiling Works and soffet (Joist and Paneling)

Drywall Partitioning Work (Studs and Paneling)

Masonry Works

Construction of CATCH BASIN

Construction of Concrete Wall and finishing of opening, lintels and slabs

Concrete wall Finishing of corners and openings

Tile Works

Installation of Floor and Wall Tiles (toilet)

Roofing Works

TRUSSES

FASCIA FRAMES

Plumbing Works

INSTALLATION OF SOIL PIPE

INSTALLATION OF WASTE PIPE

INSTALLATION OF WATER SUPPLY LINE

INSTALLATION OF PLUMBING FIXTURES (Water Closet and Urinal)

ELECTRICAL WORKS

Panel Board

LIGHTING FIXTURES

WIRES AND CABLES

WIRING DEVICES

CONDUITS

PAINTING WORKS

Walls and Columns

CEILING PAINT

Glass Works (Supply and Install)

B I L L O F Q U A N T I T I E S

1.0 GENERAL REQUIREMENTS

1.1 Mobilization/ Demobilization

1.2 Safety Occupational Hazards

SUB-TOTAL

2.0 Demolition Works

2.1 Demolition of Windows, chipping of wall and slab, (Affected Portion) 1 lot

2.1 Hauling of waste materials 1 lot

2.2 Clearing of site 1 lot

SUB-TOTAL

3.0 CARPENTRY WORKS

3.1.1 FORM WORKS 1 lot

SUB-TOTAL

3.2 FABRICATION OF MOVABLE COUNTER SINK

3.2.1 Good wood Cab door panel .60x.50m with complete accessories 6 pcs

3.2.2 High Quality Laminated Marine Plywood 3/4 x 4'x 8' 3 pcs

3.2.3 Phenolic Resin Flat Plate Sheet 18 mm x 200mm x 200mm (Beige) 1 pcs

3.2.4 Stainless Small Sink 12"x 16" 3 pcs

3.2.6 Others Consumables 1 lot

Sub-total,

3.3 Construction of Wall partition (for breast feeding area)

3.3.1 Marine Plywood 3/4 x 4'x 8'(good quality) 5 sht

3.3.2 Metal furring 1"x2" 25 lght

3.3.3 1.5"x24"x79" High Density Seat Firm Cushion Upholstery Foam 2 rolls

3.3.4 Hawaii Leather Upholstery Fabric 90cm x 70cm (yellow-Orange) 10 mts

3.3.5 Smoked glass 1/4"thk. with Alum. Casing (bronze glass finish)with complete accessories 1 lot

3.3.6 Others Consumables 1 lot

Sub-total,

3.4 FABRICATION of Padded Partition low wall

3.4.1 Door 4(Good wood @ 2"x2"x6' S4S 20 pcs

3.4.2 Hawaii Leather Upholstery Fabric 90cm x 70cm (yellow-Orange) 10 mts

3.4.3 High Density Foam (24" w x 72" h x 2" thk.) 2 rolls

3.4.4 2Pcs Durable Invisible Hidden Cross Hinge Folding Door Hinge 1 pcs

3.4.5 Others Consumables 1 lot

Sub-total,

3.5 INSTALLATION OF PANEL DOORS

- 3.5.1 Door 2 (Panel Door @ H 2.10m Xw 0.80m) 2 set
- 3.5.2 Door 3 (Panel Door H 2.10m x W 0.75m) 1 set
- 3.5.3 Door Jamb H .10m x W 0.80m 2 set
- 3.5.4 Door Jamb H 2.10mxW 0.75m 1 set
- 3.5.5 Loose Pin Hinges, U.S. 3.5" x 3 .5" 2mm brass type 9 set
- 3.5.6 Heavy Duty Hinges, U.S. 3.5" x 3 .5" For stell Gate 3 pcs
- 3.5.7 Door Knob Heavy Duty (Lever type) 5 set
- 3.5.8 Magnetic Door Holder Catch Stopper 5 set
- 3.5.9 Retroffitng of main door panel(glass window) 1 lot

SUB-TOTAL

4.0 Ceiling Works and soffet (Joist and Paneling)

- 4.1.1 Fiber Cement board 3.5mm (4'x 8') 8 sht
- 4.1.2 Acoustic Ceiling board Panel @ .60x.60 54 pcs
- 4.1.3 Metal furring 1"x2" 110 lght
- 4.1.4 Ceiling Tile Suspension System, Main Tee (24x32mmx3600mm) 8 pcs
- 4.1.5 Ceiling Tile Suspension System, Cross Tee (24x32mmx600mm) 46 pcs
- 4.1.6 Suspension sytem Wall Angle 14mm x 22mmx300mm 16 pcs
- 4.1.7 Others Consumables 1 lot

SUB-TOTAL

5.0 Drywall Partitioning Work (Studs and Paneling)

- 5.1.1 Fiber Cement board 3.5mm (4'x 8') 4 sht
- 5.1.2 Metal furring 32mm x 52mm, 0.5mm thickness 12 lght
- 5.1.3 Metal furring 32mm x 76mm, 0.8mm thickness 5 lght
- 5.1.4 Others Consumables 1 lot

SUB-TOTAL

6.0 Masonry Works

6.1 Construction of CATCH BASIN

- 6.1.1 Portland Cement 1 Bags
- 6.1.2 10 mm ø x 6 m DSB 2 Lgths
- 6.1.3 CHB 4" x 8" x 16" 20 pcs

Sub-total,

6.2 Construction of Concrete Wall and finishing of opening, lintels and slabs

- 6.2.1 CHB 4" x 8" x 16" 180 pcs
- 6.2.2 Portland Cement (40 kgs) Premium 20 bag
- 6.2.3 Mixing Sand 3 cu.m
- 6.2.4 Mixing Gravel 3/4 3 cu.m
- 6.2.5 10 mm ø x 6 m DSB 6 Lgth
- 6.2.6 Others Consumables 1 lot

SUB-TOTAL

6.3 Concrete wall Finishing of corners and openings

- 6.3.1 Portland Cement (40 kgs) Premium 2 bag
- 6.3.2 Skimcoat Superfine white (20 kgs) 6 bags
- 6.3.3 Mixing Sand 1 cu.m

Sub-total,

7.0 Tile Works

7.1 Installation of Floor and Wall Tiles (toilet)

- 7.1.1 16"x16" Ceramic Floor Tiles (Pine Mid Gray) 12 pcs
- 7.1.2 16"x16" Ceramic Walls Tiles (Pine Mid Gray) 25 pcs
- 7.1.3 Portland Cement (40 kgs) Premium 2 bag
- 7.1.4 ABC Tile Adhesive 2 bag
- 7.1.5 TILE GROUTE (verify) 2 bag

SUB-total,

8.0 Roofing Works

- 8.1.1 Twin Hi-Rib Type Long Span Green(.40x1.22x4.8) 14 sht
- 8.1.2 Ridge Roll Green (.4x.610x2.44m) 4 sht
- 8.1.3 Bended G.I Fascia Green (.4mx.915mx2.44m) 9 sht
- 8.1.4 End Flashing Green (.4mx.915mx2.44m) 8 sht
- 8.1.5 Elastomeric Sealant 1 qrt
- 8.1.6 Touch up Paint (Green) 1 qrt
- 8.1.7 Drillbit power craft 9/64 (US) 4 pcs
- 8.1.8 Texcrew (for roofing) 1250 pcs
- 8.1.9 Others Consumables 1 lot

SUB-total,

8.2 TRUSSES

- 8.2.1 C-Purlins 1.5mm 2"x6"x20' 10 lgth
- 8.2.2 C-Purlins 1.5mm 2"x3"x20' 12 lgth
- 8.2.3 10mmØ x 6m DSB 4 lgth
- 8.2.4 Welding Rod 6013 1 box
- 8.2.5 1Box(10Pcs) Tailin Super Thin Cutting Disc 4Inch (105x1.0x16mm) 2 box
- 8.2.6 Others Consumables 1 lot

SUB-TOTAL

8.3 FASCIA FRAMES

- 8.3.1 Angle steel Bar1"x1"x1/8" 10 lgth
- 8.3.2 8 mm Ø Def BARS 8 lgth
- 8.3.3 Hacksaw Blade (good quality) HS5 32TP1 1 pc
- 8.3.4 Cut Off #4 super thin 4 pc
- 8.3.5 Diamond Cutting Blade 4" 2 pc
- 8.3.6 METAL PRIMER (Zinc Chromate) 2 GALS

- 8.3.7 Lacquer Thinner 2 gal
- 8.3.8 Others Consumables 1 lot
- Sub-total,
- 9.0 Plumbing Works
- 9.1 INSTALLATION OF SOIL PIPE
- 9.1.1 PVC SANITARY PIPE(ORANGE PIPE)# 4"Ø x 10'ft. 2 pcs
- 9.1.2 Watercloset PVC Bend fettings 4" x 4" 1 pcs
- 9.1.3 PVC Wye 4" x 4" 1 pcs
- 9.1.4 PVC Wye 4" x 2" 3 pcs
- 9.1.5 Pvc Sanitary fittings Elbow 90 degrees 1/4 bend 4"Ø 2 pcs
- 9.1.6 PVC Sanitary Clean out 4" 1 pcs
- 9.1.7 PVC coupling sanitary fitting 4" 2 pcs
- 9.1.8 PVC Reducer sanitary fitting 2"-4" 2 pcs
- 9.1.9 P-trap set 1-1/2 2 pcs
- SUB-TOTAL
- 9.2 INSTALLATION OF WASTE PIPE
- 9.2.1 PVC SANITARY PIPE (ORANGE PIPE)# 2"Ø 4 pcs
- 9.2.2 Wye 2" x 2" 3 pcs
- 9.2.3 PVC coupling sanitary fitting 2" 4 pcs
- 9.2.4 PVC Sanitary Clean out 2" 2 pcs
- 9.2.5 Sink drain plug 4"x4" 3 pcs
- 9.2.6 Sanitary P-Trap 2" 3 pcs
- 9.2.7 Floor drain 4"x4" 1 pcs
- SUB-TOTAL
- 9.3 INSTALLATION OF WATER SUPPLY LINE
- 9.3.1 PE Pipe to PVC connector 3/4" Ø 1 pcs
- 9.3.2 PVC Pipe 3/4" Ø (Blue Pipe) 2 pcs
- 9.3.3 PVC Pipe 1/2" Ø (Blue Pipe) 5 pcs
- 9.3.4 PVC Fittings Elbow 90 degrees 1/2" 12 pcs
- 9.3.5 PVC Reducer 3/4" to 1/2"Ø 5 pcs
- 9.3.6 PVC Fittings Tee 3/4" 4 pcs
- 9.3.7 PVC Fittings Tee 1/2" 8 pcs
- 9.3.8 PVC coupling sanitary fitting 3/4" 5 pcs
- 9.3.9 PVC Gate Valve 1/2" 2 pcs
- 9.3.10 PVC Gate Valve 1/3" 1 pcs
- SUB-TOTAL
- 9.4 INSTALLATION OF PLUMBING FIXTURES (Water Closet and Urinal)
- 9.4.1 Water Closet with Flash Tank Porcelain set (Color White) 1 sets
- 9.4.2 Urinal Wall Mounted for Men (White) 1 pcs
- 9.4.3 Bidet head with 1.2 m PVC hose w/ holder (white) 1 pcs
- 9.4.4 Faucet lever type 3 pcs
- 9.4.5 Flexible hose 24" 5 pc
- 9.4.6 3-way Angle Valve 1/2" Ø ABS Chrome 1 pc
- 9.4.7 Angle Control Valve 1/2" Ø ABS Chrome 2 pc
- SUB-TOTAL,
- 10.0 ELECTRICAL WORKS
- 10.1 Panel Board
- 10.1.1 4-6 Circuit Household Switch Plastic Distribution Box with Mini Circuit Breaker Dustproof Waterproof Protection Box with 2-30A & 2-20A Breaker.(Surface type) with 60A Main 1 assy
- SUB-TOTAL
- 10.2 LIGHTING FIXTURES
- 10.2.1 Recessed Troffer Light 2-18watts 4inches @ day light 6 sets
- 10.2.2 Pin Lights 10watts LED Bulb with Casing @ 6"Ø Black Rim 7 sets
- 10.2.3 Transferring of electrical lights and wirings 1 lot
- SUB-TOTAL
- 10.3 WIRES AND CABLES
- 10.3.1 5.5 mm² THHN Stranded 1 rolls
- 10.3.2 3.5 mm² THHN Stranded 1 rolls
- SUB-TOTAL
- 10.4 WIRING DEVICES
- 10.4.1 Two Gang Outlet "Universal Flush Type" 6 sets
- 10.4.2 Single Switch 6 sets
- 10.4.3 Two Gang Switch 2 sets
- 10.4.4 Aircon Outlet 1 sets
- SUB-TOTAL
- 10.5 CONDUITS
- 10.5.1 Junction Box (octagonal) 15 pcs
- 10.5.2 Utility Box 10 pcs
- 10.5.3 1/2" Ø Elec. PVC Pipe 20 lgnth
- 10.5.4 PVC pipe 3/4" 5 pcs
- 10.5.5 PVC Elbow 1/2" Ø 7 pcs
- 10.5.6 Electrical tape 4 pcs
- 10.5.7 Moldflex, Flexible pipe 1/2" 5 mt
- SUB-TOTAL
- 11.0 PAINTING WORKS
- 11.1 Walls and Columns
- 11.1.1 Acrylic Latex Paint Cocoa Chlp (Premlum) 3 gal

- 11.1.2 Acrylic Latex Paint Crisp Ecru (Premium) 6 gal
- 11.1.3 Primer Latex Paint White (premium) 7 gal
- 11.1.4 Acrylic Latex Paint Clear Emulsion (Premium) 1 gal
- 11.1.5 Acrylic Latex Paint Semi-Gloss white (Premium) 2 gal
- 11.1.6 Concrete primer and sealer 4 gal
- 11.1.7 Concrete Putty 6 gal
- 11.1.8 Lacquer Thinner 2 gal
- 11.1.9 Others Consumables 1 lot
- SUB-TOTAL
- 11.2 CEILING paint
- 11.2.1 Acrylic Latex Paint Faint Silver (Premium) 4 gal
- 11.2.2 Primer Latex Paint White (premium) 2 gal
- 11.2.3 A&B Epoxy Putty 1 gal
- 11.2.4 Lacquer Thinner 1 gal
- SUB-TOTAL
- 12.0 Glass Works (Supply and Install)
- 12.1 Jalouplus Windows with Alum. Casing (bronze glass finish)0.60m width x 0.40 m height with complete accessories 1 set
- 13.2 Installation of Jalouplus window 0.40m H x 0.60m W x 6mm thk. 2 set
- Others Consumables 1 lot
- SUB-TOTAL

PROJECT DURATION: 60 CALENDAR DAYS
 Note: Attach Certificate of Site Inspection

- A. TOTAL DIRECT COST
- B. CONSUMABLES:
- C. SUPERVISION AND ADMINISTRATION:
- D. TOTAL INDIRECT COST (B+C):
- E. TOTAL COST (A+D)
- F. VAT (12% OF ITEM E):
- GRAND TOTAL OF PROJECT COST:

*****NOTHING FOLLOWS*****

TOTAL ABC = Php 499,934.41
 PROCUREMENT OF LABOR AND MATERIALS FOR PROPOSED CHILD MINDING FACILITY - ALIJIS CAMPUS/E. BUGNA
 PR# 21-320-0921 09-21-21
 MDS 214-101-21-09 09-14-21

Line Items

Item No.	Product/Service Name	Description	Quantity	UOM	Budget (PHP)
1	ONE (1) LOT	Labor and Materials for Conversion of Old Clinic to Gender and Development Child Minding Facility-Alijis Campus	1	Lot	499,934.41

Created by Rowena De la Vida Prado
Date Created 24/09/2021

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.