



PhilGEPS

Philippine Government Electronic Procurement System

Central Portal for
Philippine Government
Procurement Opportunities

[Help](#)

Bid Notice Abstract

ICT

Request for Quotation (RFQ)

Reference Number 8691569
Procuring Entity CARLOS HILADO MEMORIAL STATE COLLEGE
Title Procurement of Labor and Materials for the Repair and Enhancement of Stage at CHMSU Field - Talisay Campus
Area of Delivery Negros Occidental

Solicitation Number:	RFQ 22-187	Status	Pending
Trade Agreement:	Implementing Rules and Regulations	Associated Components	1
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	Bid Supplements	0
Classification:	Civil Works	Document Request List	0
Category:	Construction Projects	Date Published	24/05/2022
Approved Budget for the Contract:	PHP 420,000.00	Last Updated / Time	23/05/2022 17:04 PM
Delivery Period:	21 Day/s	Closing Date / Time	27/05/2022 10:00 AM
Client Agency:			
Contact Person:	Rowena De la Vida Prado Administrative Assistant II Mabini Street Talisay City Negros Occidental Philippines 6115 63-34-7124804 63-34-7128404 bac.sec@chmsc.edu.ph		

Description

Republic of the Philippines
 CARLOS HILADO MEMORIAL STATE COLLEGE
 Talisay City, Negros Occidental
 Telefax: (034) 712-8404 / 495-3767
 bac.sec@chmsc.edu.ph

REQUEST FOR QUOTATION
 Page 1 of 5
 Date: MAY 23, 2022
 Quotation No. 22-187

Please quote your lowest price on the item/s listed below, stating the shortest time of delivery and submit your quotation duly signed by your representative not later than _____ in the return envelope attached herewith.

ENGR. JUN-JUN J. MARQUEZ
 BAC Chairman

NOTE:

1. ALL ENTRIES MUST BE TYPEWRITTEN
2. DELIVERY PERIOD WITHIN _____ CALENDAR DAYS
3. WARRANTY SHALL BE FOR A PERIOD OF SIX (6) MONTHS FOR SUPPLIES & MATERIALS, ONE (1) YEAR FOR

EQUIPMENT, FROM DATE OF
OF ACCEPTANCE BY THE PROCURING ENTITY

4. PRICE VALIDITY SHALL BE FOR A PERIOD OF _____ CALENDAR DAYS
5. G-EPS REGISTRATION CERTIFICATE SHALL BE ATTACHED UPON SUBMISSION OF THE QUOTATION
6. BIDDERS SHALL SUBMIT ORIGINAL BROCHURES SHOWING CERTIFICATIONS OF THE PRODUCT BEING OFFERED

ITEM DESCRIPTION OF WORKS QTY. UNIT MATERIAL COST LABOR COST TOTAL COST
NO. Unit Cost Material Sub-Total Cost Unit Cost Labor Sub-Total Cost

ONE (1) LOT

LABOR AND MATERIALS FOR THE REPAIR AND ENHANCEMENT OF STAGE AT CHMSU FIELD - TALISAY CAMPUS

Scope of Works:

- 1.0 GENERAL REQUIREMENTS
 - 1.1 Mobilization and Demobilization
 - 1.2 Safety Occupational Hazards
 - 1.3 Site Clearing,Cleaning and Hauling
 - 1.4 Installation and Mobilization of Scaffoldings
- 2.0 ROOFING WORKS
 - 2.1 Removal of old roofing sheets, gutter and wall capping
 - 2.2 Repainting of existing rafters and purlins
 - 2.3 Installation of Roofing sheet including touch up paints and sealing of roofing sheet (Roofing materials provided by CHMSU)
 - 2.4 Installation of Gutter and Wall Capping (including sealing and waterproofing)
- 3.0 CEILING WORKS
 - 3.1 Removal of old ceiling frames and covering
 - 3.2 Installation of ceiling frames and covering
- 4.0 PAINTING WORKS
 - 4.1 Interior and exterior wall
 - 4.2 Parapet walls
 - 4.3 Ceiling
 - 4.4 Columns
 - 4.5 Plant box
 - 4.6 Railings
 - 4.7 Painting of existing roof framing
 - 4.8 Cleaning and surface preparation for all painted areas
- 5.0 TILE WORKS
 - 5.1 Replacement the defective tiles on floor and stage concrete railings
 - 5.2 Cleaning of existing tiles at floor, coulms, plant box and stage railings (pressure washer)
- 6.0 CONCRETING WORKS
 - 6.1 Concreting and finishing of damage ramps
 - 6.2 Concreting and finishing of damage portion of stage
- 7.0 WINDOWS
 - 7.1 Pull-out of existing jalousie window
 - 7.2 Installation of new 2-units Jalousie window
- 8.0 MISCELLANEOUS WORKS

BILL OF QUANTITIES

- 1.0 GENERAL REQUIREMENTS
 - 1.1 Mobilization and Demobilization 1.00 lot
 - 1.2 Safety Occupational Hazards 1.00 lot
 - 1.3 Site Clearing,Cleaning and Hauling 1.00 lot
 - 1.4 Installation and Mobilization of Scaffoldings 1.00 lot
 Sub-total, 1.0 (GENERAL REQUIREMENTS)
- 2.0 ROOFING WORKS
 - 2.1 Removal of old roofing sheets 90.00 sq.m.
 - 2.2 Removal of old gutter and wall capping 45.00 ln.m.
 - 2.3 Labor for Installation of Ribtype Roofing 90.00 sq.m.
 - 2.4 0.4mm G.I. Bended Sheet Gutter (pre-painted) 13.50 ln.m.
 - 2.5 0.4mm G.I. Bended Sheet Wall Capping (pre-painted) 30.00 ln.m.
 - 2.6 Elastomeric sealant 5.00 tube/qrt
 - 2.7 1/8" x 1" blind rivet 3.00 box
 - 2.8 Touch-up paint 1.00 lot
 Sub-total, 2.0 (ROOFING WORKS)
- 3.0 CEILING WORKS
 - 3.1 Removal of old ceiling frames and covering 135.00 sq.m.
 - 3.2 Hardilite panel (1.22mx2.44mx3.5mm thick), metal furring (0.40mm thick) spaced@0.60m O.C. Bothways and other accessories for completion 135.00 sq.m.
 Sub-total, 3.0 (CEILING WORKS)
- 4.0 PAINTING WORKS
 - 4.1 Interior and exterior wall (Semi-gloss Latex Paint) 167.00 sq.m.
 - 4.2 Parapet walls (Semi-gloss Latex Paint) 95.50 sq.m.
 - 4.3 Ceiling (Latex textured paint) 135.00 sq.m.
 - 4.4 Columns (Semi-gloss Latex Paint) 4.00 sq.m.
 - 4.5 Plant box (Semi-gloss Latex Paint) 1.00 lot

4.6 Railings (Epoxy metal paint) 1.00 lot
 4.7 Painting of existing roof framing ((Epoxy metal paint) 1.00 lot
 Sub-total, 4.0 (PAINTING WORKS)

5.0 TILE WORKS

5.1 Replacement the defective tiles on floor and stage concrete railings 1.00 lot
 5.2 Cleaning of existing tiles at floor, coulms, plant box and stage railings (pressure washer) 1.00 lot
 Sub-total, 5.0 (CEILING WORKS)

6.0 CONCRETING WORKS

6.1 Concreting and finishing of damage ramps 1.00 lot
 6.2 Concreting and finishing of damage portion of stage 1.00 lot
 Sub-total, 6.0 (CONCRETING WORKS)

7.0 WINDOWS

7.1 Pull-out of existing jalousie window 1.00 lot
 7.2 (1.50m x 2.00m) (Wx H) Analok Bronze 6mm Thick Jalouplas Window 22-blades double control and Frame with complete accessories 2.00 sets
 Sub-total, 7.0 (WINDOWS)

8.0 MISCELLANEOUS WORKS

8.1 FOR ALL OTHER ITEMS that are not included on listed Bill of Quantities in your Bid but tare deemed necessary for the completion of the works and the delivery of the project and in full compliance with all the requirements of the occupancy permit.
 Sub-total, 8.0 (MISCELLANEOUS WORKS)

PROJECT DURATION: 21 CALENDAR DAYS
 Note: Attach Certificate of Site Inspection

- A. TOTAL DIRECT COST
- B. CONSUMABLES:
- C. SUPERVISION AND ADMINISTRATION:
- D. TOTAL INDIRECT COST (B+C):
- E. TOTAL COST (A+D)
- F. VAT (12% OF ITEM E):
- GRAND TOTAL OF PROJECT COST:
- *****NOTHING FOLLOWS*****

TOTAL ABC = Php 420,000.00

PROCUREMENT OF LABOR AND MATERIALS FOR THE REPAIR AND ENHANCEMENT OF STAGE AT CHMSU FIELD - TALISAY CAMPUS/J. MARQUEZ (PPDM Director)
 PR# 22-222-0523 05-23-22
 MDS 112-101-22-05 05-19-22

Line Items

Item No.	Product/Service Name	Description	Quantity	UOM	Budget (PHP)
1	ONE (1) LOT	Labor and Materials for the Repair and Enhancement of Stage at CHMSU Field	1	Lot	420,000.00

Created by Rowena De la Vida Prado
Date Created 23/05/2022

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.