

Central Portal for Philippine Government Procurement Oppurtunities

ICT

# **Bid Notice Abstract**

# Request for Quotation (RFQ)

**Reference Number** 

8839150

**Procuring Entity** 

CARLOS HILADO MEMORIAL STATE UNIVERSITY

Title

Procurement of Labor and Materials for the Installation of Steel Frame and Cladding at

Gymnasium Stage - Talisay Campus

**Area of Delivery** 

Negros Occidental

Solicitation Number:	RFQ 22-271	Status	Pending
Trade Agreement:	Implementing Rules and Regulations		
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	Associated Components	1
Classification:	Civil Works	Bid Supplements	0
Category:	Construction Projects		
Approved Budget for the Contract:	PHP 487,715.00	Document Request List	0
Delivery Period:	30 Day/s		
Client Agency:		Date Published	15/07/2022
Contact Person:	Rowena De la Vida Prado		
	Administrative Assistant II Mabini Street Talisay City Negros Occidental	Last Updated / Time	14/07/2022 22:17 PM
	Philippines 6115 63-34-7120003 Ext.142	Closing Date / Time	19/07/2022 10:00 AM
	bac.sec@chmsc.edu.ph		

### Description

Republic of the Philippines CARLOS HILADO MEMORIAL STATE UNIVERSITY Talisay City, Negros Occidental Telefax: (034) 712-8404 / 495-3767

bac.sec@chmsc.edu.ph

REQUEST FOR QUOTATION

Page 1 of 3

Date: JULY 14, 2022 Quotation No. 22-271

Please quote your lowest price on the item/s listed belo	w, stating the shortest time of delivery and submit your
quotation duly	
signed by your representative not later than	in the return envelope attached herewith.

ENGR. JUN-JUN J. MARQUEZ BAC Chairman

NOTE:

1. ALL ENTRIES MUST BE TYPEWRITTEN

2. DELIVERY PERIOD WITHIN \_\_\_\_\_ CALENDAR DAYS

3. WARRANTY SHALL BE FOR A PERIOD OF SIX (6) MONTHS FOR SUPPLIES & MATERIALS, ONE (1) YEAR FOR EQUIPMENT, FROM DATE OF

OF ACCEPTANCE BY THE PROCURING ENTITY

4. PRICE VALIDITY SHALL BE FOR A PERIOD OF \_\_\_\_\_ CALENDAR DAYS

. G-EPS REGISTRATION CERTIFICATE SHALL BE ATTACHED UPON SUBMISSION OF THE QUOTATION

6. BIDDERS SHALL SUBMIT ORIGINAL BROCHURES SHOWING CERTIFICATIONS OF THE PRODUCT BEING OFFERED

ITEM DESCRIPTION OF WORKS QTY, UNIT MATERIAL COST LABOR COST TOTAL COST

NO. Unit Cost Material Sub-Total Cost Unit Cost Labor Sub-Total Cost

ONE (1) LOT

LABOR AND MATERIALS FOR THE INSTALLATION OF STEEL FRAME AND CLADDING AT GYMNASIUM STAGE - TALISAY CAMPUS

#### Scope of Works:

1.0 GENERAL REQUIREMENTS

- 1,1 Mobilization and Demobilization
- 1.2 Safety Occupational Hazards
- 1.3 Site Clearing, Cleaning and Hauling
- 1.4 Scaffoldings Installation and Mobilization
- 1.5 Demolition and pull out of existing stage facade structure

# 2.0 STEEL WORKS

2.1 Fabrication and installation of stage cladding and steel frames

2.2 Installation of Stainless strips on stage cladding

2.3 Fabrication and installation of catwalk and ladder steel frame

#### 3.0 MISCELLANEOUS WORKS

#### BILL OF QUANTITIES

1.0 GENERAL REQUIREMENTS

1,1 Mobilization and Demobilization 1,00 lot

1.2 Safety Occupational Hazards 1.00 lot

1.3 Site Clearing, Cleaning and Hauling 1.00 lot

1.4 Scaffoldings Installation and Mobilization 1.00 lot

1.5 Demolition and pull out of existing stage facade structure 1.00 lot Sub-total, 1.0 (GENERAL REQUIREMENTS)

# 2.0 STEEL WORKS

2.1 Stage Cladding

2.1.1 1/8" x 2" x 2" x 6m Angle Bar 32.00 lght

2.1.2 4" Ø Steel Cutting Disc 10.00 pcs

2.1.3 Expansion Bolt 5/8" x 2" 60.00 pcs

2.1.4 Welding Rod 6013 2.00 box

2.1.5 3mm x 1" x 2" x 6m Stainless 304 Angle Bar 16.00 lght

2.1.6 Metal Cladding Panel (Orange) 28.00 sht

## 2.2 Stage Vertical Ladder and Catwalk

2,2.1 1/8" x 2" x 2" x 6m Angle Bar 24.00 lght

2.2.2 4" Ø Steel Cutting Disc 15.00 pcs

2.2.3 10mm Square Bar 55.00 lght

2.2.4 Welding Rod 6013 2.00 box

2.2.5 Painting of steel frame with epoxy paint 1.00 lot

Sub-total, 2.0 (STEEL WORKS)

# 3.0 MISCELLANEOUS WORKS

FOR ALL OTHER ITEMS that are not included on listed Bill of Quantities in your Bid but tare deemed necessary for the completion of the works and the delivery of the project and in full compliance with all the requirements of the occupancy permit. 1.00 lot

Sub-total, 3.0 (MISCELLANEOUS WORKS)

PROJECT DURATION: 30 CALENDAR DAYS

Note: Attach Certificate of Site Inspection

## A. TOTAL DIRECT COST

B. CONSUMABLES:

C. SUPERVISION AND ADMINISTRATION:

D. TOTAL INDIRECT COST (B+C):

E. TOTAL COST (A+D)

F. VAT (12% OF ITEM E):

GRAND TOTAL OF PROJECT COST:

\*\*\*\*\*\*\*NOTHING FOLLOWS\*\*\*\*

TOTAL ABC = Php 487,715.00

PROCUREMENT OF LABOR AND MATERIALS FOR THE INSTALLATION OF STEEL FRAME AND CLADDING AT GYMNASIUM STAGE. - TALISAY CAMPUS/J. MARQUEZ PR# 22-316-0713 07-13-22 INCOME 159-164-22-07 07-11-22 **Line Items** Product/Service Quantity UOM Budget (PHP) Item No. Description Name 487,715.00 LABOR AND MATERIALS FOR THE 1 Lot 1 ONE (1) LOT INSTALLATION OF STEEL FRAME AND CLADDING AT GYMNASIUM STAGE.

Created by Rowena De la Vida Prado

**Date Created** 14/07/2022

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.

© 2004-2022 DBM Procurement Service. All rights reserved.

Help | Contact Us | Sitemap