



Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number 9147043
Procuring Entity CARLOS HILADO MEMORIAL STATE UNIVERSITY
Title Procurement of Two (2) Units Air-Conditioning Units for CAS Office and Faculty Room - Talisay Campus
Area of Delivery Negros Occidental

Solicitation Number:	RFQ 22-441	Status	Pending
Trade Agreement:	Implementing Rules and Regulations		
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	Associated Components	1
Classification:	Goods	Bid Supplements	0
Category:	Airconditioning and Airconditioning Systems		
Approved Budget for the Contract:	PHP 338,000.00	Document Request List	0
Delivery Period:	21 Day/s		
Client Agency:		Date Published	22/10/2022
Contact Person:	Rowena De la Vida Prado Administrative Assistant II Mabini Street Talisay City Negros Occidental Philippines 6115 63-34-7120003 Ext.142 bac.sec@chmsc.edu.ph	Last Updated / Time	21/10/2022 14:53 PM
		Closing Date / Time	26/10/2022 09:00 AM

Description

Republic of the Philippines
 CARLOS HILADO MEMORIAL STATE UNIVERSITY
 Talisay City, Negros Occidental
 Telefax: (034) 712-8404 / 712-0003 Local 142
 bac.sec@chmsc.edu.ph

REQUEST FOR QUOTATION
 PAGE 1 OF 2
 Date: OCTOBER 20, 2022
 Quotation No. 22-441

Please quote your lowest price on the item/s listed below, stating the shortest time of delivery and submit your quotation duly signed by your representative not later than _____ in the return envelope attached herewith.

ENGR. JUN-JUN J. MARQUEZ
 BAC Chairman

NOTE:

- ALL ENTRIES MUST BE TYPEWRITTEN
- DELIVERY PERIOD WITHIN _____ CALENDAR DAYS
- WARRANTY SHALL BE FOR A PERIOD OF SIX (6) MONTHS FOR SUPPLIES & MATERIALS, ONE (1) YEAR FOR EQUIPMENT, FROM DATE OF ACCEPTANCE BY THE PROCURING ENTITY
- PRICE VALIDITY SHALL BE FOR A PERIOD OF _____ CALENDAR DAYS
- G-EPS REGISTRATION CERTIFICATE SHALL BE ATTACHED UPON SUBMISSION OF THE QUOTATION
- BIDDERS SHALL SUBMIT ORIGINAL BROCHURES SHOWING CERTIFICATIONS OF THE PRODUCT BEING OFFERED

ITEM ITEM & DESCRIPTION QTY. UNIT UNIT PRICE TOTAL PRICE
 NO. (Pls. indicate brand offered)
 1 Air-Conditioning Unit, Floor Mounted Split type with Installation and Testing 2 unit
 INVERTER TYPE
 3 Tonner, Capacity: 38, 000kJ/h, Voltage/Frequency: 230V, 60Hz
 Current: 16.5A ; Power: 3, 600W Max. Current: 21.0A
 Refrigerant: 1.50kg (52.9oz)(R32)/(R410A)
 Remote with Auto swing function Digital Display of Temperature.
 Controls - Soft Touch panel Long distance and high elevation pipe
 Anti-Bacteria filter; Self diagnosis function
 Includes:
 Labor, Materials and Commissioning
 Installation of A/C unit (ACCU and AHU)
 Installation of piping, includes white tape and rubber insulation
 Installation of Circuit Breaker with enclosure at ACCU
 Installation of Wiring -
 Installation of Drainage System of AHU
 Fabrication and installation of bracket for the AHU / ACCU
 Fabrication of Grills for the ACCU/Outdoor unit / SERVICE AREA
 includes ledge or catwalk installation for servicing purposes
 Vacuuming of System
 Charging of Refrigerant
 Testing and Commissioning
 Preventive Maintenance of AHU and ACCU at 2x per year, for 5 years
 includes 10x Preventive Maintenance of AHU & ACCU for 5 years
 During the installation of ACCU the supplier will pull-out the glass window
 and return the glass window after the installation
 Warranty; 1 year for Parts and 5 years Compressor Must be a AUTHORIZED SERVICE CENTER.
 NOTE:
 Supplier must proceed to actual site location during the quotation
 for the Ocular Inspection and Coordinate with the END-USER,
 BAC Secretariat, TWG-RAC for the actual location of AHU,
 ACCU and actual estimation of piping and electrical wires.
 *****Nothing Follows*****
 TOTAL ABC = Php 338,000.00
 PROCUREMENT OF AIR CONDITIONING UNIT FOR CAS OFFICE AND FACULTY ROOM USE -TALISAY CAMPUS/A.
 ALVARADO
 PR# 22-486-0928 09-28-22
 INCOME 213-164-22-09 09-26-22

Line Items

Item No.	Product/Service Name	Description	Quantity	UOM	Budget (PHP)
1	Air-conditioning Unit	Floor Mounted Split type with Installation and Testing INVERTER TYPE 3 Tonner, Capacity: 38, 000kJ/h, Voltage/Frequency: 230V, 60Hz Current: 16.5A ; Power: 3, 600W Max. Current: 21.0A Refrigerant: 1.50kg (52.9oz)(R32)/(R41	2	Unit	338,000.00

Created by Rowena De la Vida Prado
Date Created 21/10/2022

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.