



## Bid Notice Abstract

### Request for Quotation (RFQ)

**Reference Number** 9815280  
**Procuring Entity** CARLOS HILADO MEMORIAL STATE UNIVERSITY  
**Title** Procurement of Labor and Materials for the Conversion of Aqua Laboratory Into School Canteen - Phase 2 at Binalbagan Campus  
**Area of Delivery** Negros Occidental

<b>Solicitation Number:</b>	RFQ 23-227	<b>Status</b>	Pending
<b>Trade Agreement:</b>	Implementing Rules and Regulations	<b>Associated Components</b>	1
<b>Procurement Mode:</b>	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	<b>Bid Supplements</b>	0
<b>Classification:</b>	Civil Works	<b>Document Request List</b>	0
<b>Category:</b>	Construction Projects	<b>Date Published</b>	03/06/2023
<b>Approved Budget for the Contract:</b>	PHP 350,000.00	<b>Last Updated / Time</b>	02/06/2023 11:53 AM
<b>Delivery Period:</b>	60 Day/s	<b>Closing Date / Time</b>	09/06/2023 10:00 AM
<b>Client Agency:</b>			
<b>Contact Person:</b>	Rowena De la Vida Prado Administrative Assistant II Mabini Street Talisay City Negros Occidental Philippines 6115 63-34-7120003 Ext.142 bac.sec@chmsc.edu.ph		

#### Description

Republic of the Philippines  
 CARLOS HILADO MEMORIAL STATE UNIVERSITY  
 Talisay City, Negros Occidental  
 Telefax: (034) 712-8404 / 712-0003 Local 142  
 bac.sec@chmsc.edu.ph

REQUEST FOR QUOTATION  
 Page 1 of 7  
 Date: May 31, 2023  
 Quotation No. 23-227

Please quote your lowest price on the item/s listed below, stating the shortest time of delivery and submit your quotation duly signed by your representative not later than \_\_\_\_\_ in the return envelope attached herewith.

DR. ANDREW EUSEBIO S.TAN  
 BAC Chairman

#### NOTE:

1. ALL ENTRIES MUST BE TYPEWRITTEN
2. DELIVERY PERIOD WITHIN \_\_\_\_\_ CALENDAR DAYS
3. WARRANTY SHALL BE FOR A PERIOD OF SIX (6) MONTHS FOR SUPPLIES & MATERIALS, ONE (1) YEAR FOR EQUIPMENT, FROM DATE OF ACCEPTANCE BY THE PROCURING ENTITY

4. PRICE VALIDITY SHALL BE FOR A PERIOD OF \_\_\_\_\_ CALENDAR DAYS
5. G-EPS REGISTRATION CERTIFICATE SHALL BE ATTACHED UPON SUBMISSION OF THE QUOTATION
6. BIDDERS SHALL SUBMIT ORIGINAL BROCHURES SHOWING CERTIFICATIONS OF THE PRODUCT BEING OFFERED

ITEM DESCRIPTION OF WORKS QTY. UNIT MATERIAL COST LABOR COST TOTAL COST

NO. Unit Cost Material Sub-Total Cost Unit Cost Labor Sub-Total Cost

ONE (1) LOT

LABOR AND MATERIALS FOR THE CONVERSION OF AQUA LAB. INTO SCHOOL CANTEEN- PHASE 2 AT BINALBAGAN CAMPUS

Scope of Works:

1.0 GENERAL REQUIREMENTS

1.1 Mobilization and Demobilization

1.2 Temporary Facilities

1.3 Site Clearing, Hauling and Grubbing

1.3.1 Cleaning of whole area before and after construction, cleaning of existing windows

1.4 Safety Occupational Hazards

2.0 STRUCTURAL WORKS

2.1 Roofing Works

2.1.1 Removal of existing :

2.1.1.1 Roofing sheets and accessories(112 sq.m) , damaged trusses (LABOR)

Roofing sheets and accessories , damaged ceiling joist and trusses

2.2 Installation/Replacement :

2.2.1 Replacement of damaged wooden trusses and damaged window sill, scaffoldings

(materials to be provided by CHMSU)(LABOR)

2.3 Installation of roofing sheets and accessories ,ridge roll (LABOR and materials )

,ridge roll (LABOR and materials )

3.0 ARCHITECTURAL WORKS

3.1 CEILING WORKS

3.1.1 Removal of existing

3.1.1.1 ceiling ,ceiling joist(126 sq.m) (LABOR)

3.2.1 replacement of ceiling panels, ceiling frames

/joist, installation of catwalk and hanger,

ceiling hanger(LABOR and materials )

3.2 PAINTING WORKS

3.2.1 Painting of ceiling (LABOR and materials )

3.3 WINDOWS

3.3.1 Removal existing:

3.3.1.1 Existing Doors and Windows and window sill (LABOR )

3.3.2 Installation/Replacement of doors and windows (LABOR & MATERIALS)

3.3.2.1 W1 - Sliding window(3.50m w x 1.20m h ) clear glass with Aluminum frame window powder coated ( see plan details) (LABOR & MATERIALS)

4.0 ELECTRICAL WORKS

4.1 Installation of new lighting and accessories, wires/cables ,switches (LABOR & MATERIALS)

5.0 MISCELLANEOUS WORKS

BILL OF QUANTITIES

1.0 GENERAL REQUIREMENTS

1.1 Mobilization and Demobilization 1.00 lot

1.1.1 Temporary Facilities, 1.00 lot

1.1.2 Site clearing, hauling and grubbing

1.1.3 cleaning of whole area before and after construction , cleaning of existing windows 1.00 lot

1.1.4 Safety Occupational Hazards 1.00 lot

Sub-total, 1.0 (GENERAL REQUIREMENTS)

2.0 STRUCTURAL WORKS

2.1 ROOFING WORKS 1.00 lot

2.1.1 Removal of existing

2.1.1.1 Roofing sheets and accessories(112 sq.m) , and damaged trusses ( (LABOR) 1.00 lot

2.2 Installation/Replacement :

2.2.1 Replacement of damaged wooden trusses,ceiling joist and damaged window sill, scaffoldings (materials to be provided by CMHSU) (LABOR ) 1 lot

Sub-total, 2.1.1,2.2(Removal of existing and Installation/Replacement (LABOR )

2.3 Installation of roofing sheets and accessories ,ridge roll (LABOR and materials )

2.3.1 .5mm x 1.05 x 5.20m corrugated long span roofing(pre-painted) 22 sheets

2.3.2 .5mm x 0.914 x 8' Ridge roll (pre-painted) 7 sheets

2.3.3 2 1/2" full thread tekscrew 500 pc

2.3.4 Elastomeric sealant 10 tube/qrt

Sub-total, 2.3(Installation of roofings , ridge roll,replacement of damaged trusses (LABOR and materials )

Sub-total, 2.0 ROOFING WORKS(STRUCTURAL WORKS

3.0 ARCHITECTURAL WORKS

3.1 CEILING WORKS

3.1.1 Removal of existing

3.1.1.1 ceiling ,ceiling joist(126 sq.m) (LABOR) 1 lot

3.2.1 replacement of ceiling panels,ceiling frames/joist ,Installation of catwalk and hanger,ceiling hanger,brackets