



Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number 13107218
Procuring Entity CARLOS HILADO MEMORIAL STATE UNIVERSITY
Title Procurement of Airconditioning Units with Installation for the Smart Classrooms for the Talisay, Fortune-Towne and Binalbagan Campuses
Area of Delivery Negros Occidental

Solicitation Number:	RFQ 26-281	Status	Active
Trade Agreement:	Implementing Rules and Regulations	Associated Components	1
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 34)	Bid Supplements	0
Classification:	Goods	Document Request List	1
Category:	Airconditioning and Airconditioning Systems	Date Published	05/07/2026
Approved Budget for the Contract:	PHP 360,000.00	Last Updated / Time	05/07/2026 00:00 AM
Delivery Period:	30 Day/s	Closing Date / Time	13/07/2026 17:00 PM
Client Agency:			
Contact Person:	Rowena De la Vida Prado Administrative Assistant II Mabini Street Talisay City Negros Occidental Philippines 6115 63-34-7120005 Ext.142 63-939-9296624 bac.sec@chmsu.edu.ph		

Description

Republic of the Philippines
 CARLOS HILADO MEMORIAL STATE UNIVERSITY
 Talisay City, Negros Occidental
 Cell Phone #: 09205833046
 bac.sec@chmsu.edu.ph

REQUEST FOR QUOTATION

Date: JULY 1, 2026
 Quotation No. 26-281

. PAGE 1 OF 2

Please quote your lowest price on the item/s listed below, stating the shortest time of delivery and submit your quotation duly signed by your representative not later than _____ in the return envelope attached herewith.

DR. MA RIZA T. MANALO
 BAC Chairman

NOTE:

1. ALL ENTRIES MAY BE TYPEWRITTEN OR LEGIBLY HANDWRITTEN
2. DELIVERY PERIOD WITHIN 30 CALENDAR DAYS
3. WARRANTY SHALL BE FOR A PERIOD OF SIX (6) MONTHS FOR SUPPLIES & MATERIALS, ONE (1) YEAR FOR EQUIPMENT, FROM DATE OF ACCEPTANCE BY THE PROCURING ENTITY
4. PRICE VALIDITY SHALL BE FOR A PERIOD OF _____ CALENDAR DAYS

5. G-EPS REGISTRATION CERTIFICATE SHALL BE ATTACHED UPON SUBMISSION OF THE QUOTATION
 6. BIDDERS SHALL SUBMIT ORIGINAL BROCHURES SHOWING CERTIFICATIONS OF THE PRODUCT BEING OFFERED

ITEM ITEM & DESCRIPTION QTY. UNIT UNIT PRICE TOTAL PRICE

NO. (Pls. indicate brand offered)

ONE (1) LOT

1 AIRCONDITIONING UNIT, With installation & testing, wall mounted 6 unit

Talisay Campus - 2 units, Fortune Towne Campus- 2 units

Binalbagan Campus - 2 units

Specifications: 2.0HP, Inverter type, 1PH, 230V, 60Hz, 18,000 -

24,000 Btu/h, EER: 11.0-14.0, System Current: 4.95 (1.25 -5.9) A

Refrigerant: R32, Remote with Auto swing Function, digital display

of temperature. Advance Nano Filtration system, anti-bacteria

filter; self-diagnosis function.

includes: labor, materials and commissioning

installation of A/C unit (ACCU and AHU)

Installation of piping, includes white tape and rubber insulation

installation of circuit breaker with enclosure at ACCU

Installation of power supply from tapping point

installation of drainage system AHU

Fabrication and installation of bracket for the AHU / ACCU

fabrication of grilles for the ACCU/Outdoor unit

vacuum system, charging of refrigerant, Testing and

commissioning, restoration works, service report upon completion

Warranty: at least 1 year for the parts and workmanship, and

5-10 years for compressor

NOTE: must be an authorized service center, the supplier must

conduct and ocular inspection at the project

30 days delivery period

terms and condition:

1. supply, delivery, installation, testing and commissioning shall be on turnkey basis.

2. all wall penetration, drilling works, and affected areas shall be properly sealed, repaired, and restored after installation.

3. existing smart classroom equipment, ICT devices, electrical facilities and network facilities shall be protected from damage, dust, moisture, and debris during installation.

4. any damage resulting from the installation works shall be repaired or replaced by the contractor at no additional cost to university.

5. the installation shall be neat, safe, and compliant with applicable electrical and building standards.

Note: Must be authorized service center

TOTAL

*****Nothing Follows*****

TOTAL ABC = Php 360,000.00

PROCUREMENT OF AIRCONDITIONING UNIT FOR THE SMART CLASSROOM OF 3 CAMPUSES - TALISAY, FORTUNE

TOWNE & BINALBAGAN CAMPUS/R. DELA TORRE

PR# 26-533-0615 06-15-26

INCOME 311-164-26-06 06-23-26

Line Items

Item No.	Product/Service Name	Description	Quantity	UOM	Budget (PHP)
1	ONE (1) LOT	AIR-CONDITIONING UNIT with Installation	6	Unit	360,000.00

Created by Rowena De la Vida Prado

Date Created 04/07/2026

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.



REQUEST FOR QUOTATION

Date: JULY 1, 2026
 Quotation No. 26-281

PAGE 1 OF 2

Please quote your lowest price on the item/s listed below, stating the shortest time of delivery and submit your quotation duly signed by your representative not later than _____ in the return envelope attached herewith.

DR. MA RIZA T. MANALO
 BAC Chairman

NOTE:

- ALL ENTRIES MAY BE TYPEWRITTEN OR LEGIBLY HANDWRITTEN
- DELIVERY PERIOD WITHIN 30 CALENDAR DAYS
- WARRANTY SHALL BE FOR A PERIOD OF SIX (6) MONTHS FOR SUPPLIES & MATERIALS, ONE (1) YEAR FOR EQUIPMENT, FROM DATE OF ACCEPTANCE BY THE PROCURING ENTITY
- PRICE VALIDITY SHALL BE FOR A PERIOD OF _____ CALENDAR DAYS
- G-EPS REGISTRATION CERTIFICATE SHALL BE ATTACHED UPON SUBMISSION OF THE QUOTATION
- BIDDERS SHALL SUBMIT ORIGINAL BROCHURES SHOWING CERTIFICATIONS OF THE PRODUCT BEING OFFERED

ITEM NO.	ITEM & DESCRIPTION (Pls. indicate brand offered)	QTY.	UNIT	UNIT PRICE	TOTAL PRICE
	ONE (1) LOT				
1	AIRCONDITIONING UNIT ,With installation & testing,wall mounted <i>Talisay Campus - 2 units, Fortune Towne Campus- 2 units</i> <i>Binalbagan Campus - 2 units</i> Specifications: 2.0HP, Inverter type, 1PH, 230V, 60Hz, 18,000 - 24,000 Btu/h, EER: 11.0-14.0, System Current: 4.95 (1.25 -5.9) A Refrigerant: R32, Remote with Auto swing Function,digital display of temperature. Advance Nano Filtration system, anti-bacteria filter; self diagnosis function. Includes: labor, materials amd commisioning Installation of A/C unit (ACCU and AHU) Installation of piping, includes white tape and rubber insulation Installation of circuit breaker with enclosure at ACCU Installation of power supply from tapping point installation of drainage system AHU Fabrication and installation of bracket for the AHU / ACCU fabrication of grilles for the ACCU/Outdoor unit vacuum system, charging of refrigerant, Testing and commisioning, restoration works,service report upon completion Warranty: atleast 1 year for the parts and workmanship, and 5-10 years for compressor NOTE: must be an authorized service center, the supplie must conduct and ocular inspection at the project 30 days delivery period terms and condition: 1. supply, delivery, installation, testing and commisioning shall be on turnkey basis. 2. all wall penetration, drilling works, and affected areas shall be properly sealed, repaired, and restored after installation. 3. existing smart classroom equipment, ICT devices, electrical	6	unit		

Date _____ By _____

Printed Name/Signature _____

Released (BAC) _____
 Returned (Supplier) _____

Tel. No./Cellphone No. _____

Date _____

